AREA STATEMENT

Plot Area = 178.96 -X 224.75	=	40,221.26	SQM.
Ground Coverage (Maximum Permissible) @ 30% of plot area	=	12,066.378	SQM.
Permissible FAR @ 2.75 of plot area	=	110,608.465	SQM. ---- (A)
Purchasable FAR @ 0.75 of plot area	=	30,165.945	SQM. ---- (B)
total FAR (2.75+0.75=3.5 of plot area)	=	140,774.410	SQM.
5% of Green building FAR at 3.5 FAR.	=	7,038.721	SQM. ---- (C)
Total permissible FAR. (A + B + C)	=	**147,813.13**	SQM.
Permissible Services @ 15% of 3.5 FAR	=	21,116.162	SQM.
Permissible commercial FAR @1% of 3.5 FAR	=	1,407.74	SQM.
Proposed Achieved FAR	=	**146249.610**	SQM.
Proposed Ground coverage (INCLUDIND GUARD RM., METER RM & PANEL RM.)	=	**8,566.313**	SQM.
Proposed Services	=	**16,803.02**	SQM.
community facility area detail (FAR)			
A. Community Building	=	1490.431	SQM.
B. Community at 2nd floor of tower 10	=	711.965	SQM.
total (A + B)	=	**2202.396**	SQM.
proposed commercial FAR area detail			
A. commercial FAR at (GR. & 1ST floor of tower 10)	=	1098.445	SQM.
B. commercial FAR of restaurant (31th floor, tower no10)	=	228.129	SQM.
Total commercial FAR (A + B)	=	**1326.574**	SQM.
permissible density @ 1650 person / hectare	=	6636.5	PPL. PERM.
total Achieved population	=	**6057**	person
PARKING CALCULATION			
required parking = perm. FAR/80 = 147813.13 /'80 = 1847.66 say	=	**1848**	**ECS . required**
proposed parking			
A. Parking in upper Basement	=	1017.9	ECS.
B. Parking in lower Basement	=	1044.3	ECS.
C. surface parking	=	66	ECS
total proposed parking (A + B + C + D)	=	**2128.2**	**ECS. Provided**

Combine Area Detail

FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
FAR IN BSMT.-1	473.281	0	473.281	10.534	462.747	
GROUND FL.	8590.525	137.625	8452.9	332.750	8120.150	0
1ST FLOOR	7077.297	680.775	6396.522	424.083	5972.439	0
2nd FLOOR	6869.525	17.705	6851.82	482.674	6369.146	0
(SERVICE FL.)	513.036	17.705	495.331	0.000	0.000	495.331
3RD FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
4th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
5th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
6th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
7th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
8th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
9th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
10th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
11th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
12th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
13th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
14th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
15th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
16th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
17th FLOOR	6545.884	17.705	6528.179	479.273	6048.906	0
18th FLOOR	6391.03	17.705	6373.325	479.273	5894.052	0
19th FLOOR	2979.187	17.705	2961.482	257.624	2703.858	0
20th FLOOR	2979.187	17.705	2961.482	257.624	2703.858	0
21st FLOOR	2979.187	17.705	2961.482	257.624	2703.858	0
22nd FLOOR	2979.187	17.705	2961.482	257.624	2703.858	0
23rd FLOOR	2979.187	17.705	2961.482	257.624	2703.858	0
24th FLOOR	2965.337	17.705	2947.632	253.270	2694.362	0
25th FLOOR	2810.483	17.705	2792.778	253.270	2539.508	0
26th FLOOR	2043.773	17.705	2026.068	165.340	1860.728	0
27th FLOOR	2043.773	17.705	2026.068	165.340	1860.728	0
28th FLOOR	2043.773	17.705	2026.068	165.340	1860.728	0
29th FLOOR	2043.773	17.705	2026.068	165.340	1860.728	0
30th FLOOR	1396.107	17.705	1378.402	113.911	1264.491	0
31st FLOOR	1218.615	17.705	1200.91	109.511	1091.399	0
MUMTY/MCH.	970.686	0	970.686	970.686	0.000	0
Upper Bsmt.	35520.74	0	35520.74	1415.176	0	34105.564
Lower Bsmt.	35520.74	0	35520.74	2657.517	0	32863.223
METER ROOM	12.58	0	12.58	0	12.58	
PANEL ROOM	42.905	0	42.905	42.905	0	
GUARD ROOM	57.928	0	57.928	57.928	0	
TOTAL	**231884**	**1367.255**	**230516.747**	**16803.019**	**146249.610**	**67464.118**

FLOOR NAME	TOWER -1 UNITS	TOWER -1 SR. UNITS	TOWER -2 UNITS	TOWER -2 SR. UNITS	TOWER -3 UNITS	TOWER -3 SR. UNITS	TOWER -4 UNITS	TOWER -4 SR. UNITS	TOWER -5 UNITS	TOWER -5 SR. UNITS	TOWER -6 UNITS	TOWER -6 SR. UNITS	TOWER -7 UNITS	TOWER -7 SR. UNITS	TOWER -8 UNITS	TOWER -8 SR. UNITS	TOWER -9 UNITS	TOWER -9 SR. UNITS	TOWER -10 UNITS	TOWER -10 SR. UNITS
GROUND FL	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6		
1ST FL.	4	4					4	4			4	4					4	4		
2nd FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6		
3rd FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
4th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
5th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
6th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
7th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
8th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
9th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
10th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
11th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
12th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
13th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
14th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
15th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
16th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
17th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
18th FL.	6	6					6	6	2	2	6	6	2	2	2	2	6	6	8	
19th FL.									2	2			2	2	2	2	6	6	8	
20th FL									2	2			2	2	2	2	6	6	8	
21st FL.									2	2			2	2	2	2	6	6	8	
22nd FL.									2	2			2	2	2	2	6	6	8	
23rd FL.									2	2			2	2	2	2	6	6	8	
24th FL.									2	2			2	2	2	2	6	6	8	
25th FL.									2	2							6	6	8	
26th FL.									2	2							6	6	8	
27th FL.									2	2							6	6	8	
28th FL.									2	2							6	6	8	
29th FL.									2	2							6	6	8	
30th FL.																	6	6	8	
31st FL.																	6	6		
TOTAL	**112**		**34**		**34**		**112**		**58**		**112**		**48**		**48**		**190**		**224**	
TOTAL		**112**		**34**		**34**		**112**		**58**		**112**		**48**		**48**		**190**		

PERM. POPULATION = 1650 PPL. / HAC.
PLOT AREA = 40,221.00 = 4.0221 HACTARE
= 6,636.47 PEOPLE

TOTAL UNITS = 972 DU.
TOTAL SR. UNITS = 748 DU.

PROPOSED POPULATION = 972 X 4.5 = 4374 PEOPLE
748 X 2.25 = 1683 PEOPLE
TOTAL = 6057 PEOPLE PROPOSRD

Tower - 1 Area Detail

Sl. No.	FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
1	FAR IN BSMT.-1						
2	GROUND FL	1053.174		1053.174	34.856	1018.318	
3	1ST FLOOR	878.307		878.307	52.548	825.759	
4	2nd FLOOR	906.405		906.405	43.135	863.270	
5	(SERVICE FL.)						
6	3RD FLOOR	906.405		906.405	43.135	863.270	
7	4th FLOOR	906.405		906.405	43.135	863.270	
8	5th FLOOR	906.405		906.405	43.135	863.270	
9	6th FLOOR	906.405		906.405	43.135	863.270	
10	7th FLOOR	906.405		906.405	43.135	863.270	
11	8th FLOOR	906.405		906.405	43.135	863.270	
12	9th FLOOR	906.405		906.405	43.135	863.270	
13	10th FLOOR	906.405		906.405	43.135	863.270	
14	11th FLOOR	906.405		906.405	43.135	863.270	
15	12th FLOOR	906.405		906.405	43.135	863.270	
16	13th FLOOR	906.405		906.405	43.135	863.270	
17	14th FLOOR	906.405		906.405	43.135	863.270	
18	15th FLOOR	906.405		906.405	43.135	863.270	
19	16th FLOOR	906.405		906.405	43.135	863.270	
20	17th FLOOR	906.405		906.405	43.135	863.270	
21	18th FLOOR	906.405		906.405	43.135	863.270	
22	19th FLOOR						
23	20th FLOOR						
24	21st FLOOR						
25	22nd FLOOR						
26	23rd FLOOR						
27	24th FLOOR						
28	25th FLOOR						
29	26th FLOOR						
30	27th FLOOR						
31	28th FLOOR						
32	29th FLOOR						
33	30th FLOOR						
34	31st FLOOR						
35	MUMTY/MCH	93.816		93.816	93.816		
36	TOTAL	17434.182		17434.182	914.515	16519.667	
37	TOTAL X NOS	17434.182	0.000	17434.182	914.515	16519.667	0.000

Tower No- 2 &3 Area Detail

FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
GROUND FL	590.141		590.141	18.698	571.442	
1ST FLOOR	417.473		417.473	25.436	392.037	
2nd FLOOR	467.707		467.707	46.142	421.565	
3RD FLOOR	467.707		467.707	46.142	421.565	
4th FLOOR	467.707		467.707	46.142	421.565	
5th FLOOR	467.707		467.707	46.142	421.565	
6th FLOOR	467.707		467.707	46.142	421.565	
7th FLOOR	467.707		467.707	46.142	421.565	
8th FLOOR	467.707		467.707	46.142	421.565	
9th FLOOR	467.707		467.707	46.142	421.565	
10th FLOOR	467.707		467.707	46.142	421.565	
11th FLOOR	467.707		467.707	46.142	421.565	
12th FLOOR	467.707		467.707	46.142	421.565	
13th FLOOR	467.707		467.707	46.142	421.565	
14th FLOOR	467.707		467.707	46.142	421.565	
15th FLOOR	467.707		467.707	46.142	421.565	
16th FLOOR	467.707		467.707	46.142	421.565	
17th FLOOR	460.782		460.782	43.965	416.817	
18th FLOOR	383.355		383.355	43.965	339.39	
19th FLOOR						
20th FLOOR						
21st FLOOR						
22nd FLOOR						
23rd FLOOR						
24th FLOOR						
25th FLOOR						
26th FLOOR						
27th FLOOR						
28th FLOOR						
29th FLOOR						
30th FLOOR						
31st FLOOR						
MUMTY/MCH	106.582		106.582	106.582		
TOTAL	8853.938		8853.938	930.777	8023.161	
TOTAL X NOS	17707.876	0	17707.876	1861.554	16046.322	0

Tower No- 4&6 Area Detail

FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
GROUND FL	994.585		994.585	64.165	930.420	
1ST FLOOR	798.924		798.924	54.873	743.451	
2nd FLOOR	869.364		869.364	45.292	824.072	
3RD FLOOR	869.364		869.364	45.292	824.072	
4th FLOOR	869.364		869.364	45.292	824.072	
5th FLOOR	869.364		869.364	45.292	824.072	
6th FLOOR	869.364		869.364	45.292	824.072	
7th FLOOR	869.364		869.364	45.292	824.072	
8th FLOOR	869.364		869.364	45.292	824.072	
9th FLOOR	869.364		869.364	45.292	824.072	
10th FLOOR	869.364		869.364	45.292	824.072	
11th FLOOR	869.364		869.364	45.292	824.072	
12th FLOOR	869.364		869.364	45.292	824.072	
13th FLOOR	869.364		869.364	45.292	824.072	
14th FLOOR	869.364		869.364	45.292	824.072	
15th FLOOR	869.364		869.364	45.292	824.072	
16th FLOOR	869.364		869.364	45.292	824.072	
17th FLOOR	869.364		869.364	45.292	824.072	
18th FLOOR	869.364		869.364	45.292	824.072	
19th FLOOR						
20th FLOOR						
21st FLOOR						
22nd FLOOR						
23rd FLOOR						
24th FLOOR						
25th FLOOR						
26th FLOOR						
27th FLOOR						
28th FLOOR						
29th FLOOR						
30th FLOOR						
31st FLOOR						
MUMTY/MCH	93.816		93.816	93.816		
TOTAL	16665.913		16665.913	982.818	15683.095	
TOTAL X NOS	33331.826	0	33331.826	1965.636	31366.19	0

Tower No - 5 Area Detail

FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
GROUND FL	747.209		747.209	19.92	727.289	
1ST FLOOR	747.209	307.306	439.903	33.79	406.113	
2nd FLOOR	647.666		647.666	51.429	596.237	
3RD FLOOR	647.666		647.666	51.429	596.237	
4th FLOOR	647.666		647.666	51.429	596.237	
5th FLOOR	647.666		647.666	51.429	596.237	
6th FLOOR	647.666		647.666	51.429	596.237	
7th FLOOR	647.666		647.666	51.429	596.237	
8th FLOOR	647.666		647.666	51.429	596.237	
9th FLOOR	647.666		647.666	51.429	596.237	
10th FLOOR	647.666		647.666	51.429	596.237	
11th FLOOR	647.666		647.666	51.429	596.237	
12th FLOOR	647.666		647.666	51.429	596.237	
13th FLOOR	647.666		647.666	51.429	596.237	
14th FLOOR	647.666		647.666	51.429	596.237	
15th FLOOR	647.666		647.666	51.429	596.237	
16th FLOOR	647.666		647.666	51.429	596.237	
17th FLOOR	647.666		647.666	51.429	596.237	
18th FLOOR	647.666		647.666	51.429	596.237	
19th FLOOR						
20th FLOOR						
21st FLOOR						
22nd FLOOR						
23rd FLOOR						
24th FLOOR						
25th FLOOR						
26th FLOOR						
27th FLOOR						
28th FLOOR						
29th FLOOR						
30th FLOOR						
31st FLOOR						
MUMTY/MCH	67.423		67.423	67.423		
TOTAL	19696.489	307.306	19389.183	1561.145	17828.038	
TOTAL X NOS	19696.489	307.306	19389.183	1561.145	17828.038	0

Tower No - 7 & 8 Area Detail

FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
GROUND FL	590.141		590.141	14.357	575.784	
1ST FLOOR	397.473		397.473	18.155	379.318	
2nd FLOOR	467.707		467.707	46.142	421.565	
3RD FLOOR	467.707		467.707	46.142	421.565	
4th FLOOR	467.707		467.707	46.142	421.565	
5th FLOOR	467.707		467.707	46.142	421.565	
6th FLOOR	467.707		467.707	46.142	421.565	
7th FLOOR	467.707		467.707	46.142	421.565	
8th FLOOR	467.707		467.707	46.142	421.565	
9th FLOOR	467.707		467.707	46.142	421.565	
10th FLOOR	467.707		467.707	46.142	421.565	
11th FLOOR	467.707		467.707	46.142	421.565	
12th FLOOR	467.707		467.707	46.142	421.565	
13th FLOOR	467.707		467.707	46.142	421.565	
14th FLOOR	467.707		467.707	46.142	421.565	
15th FLOOR	467.707		467.707	46.142	421.565	
16th FLOOR	467.707		467.707	46.142	421.565	
17th FLOOR	467.707		467.707	46.142	421.565	
18th FLOOR	467.707		467.707	46.142	421.565	
19th FLOOR						
20th FLOOR						
21st FLOOR						
22nd FLOOR						
23rd FLOOR						
24th FLOOR						
25th FLOOR						
26th FLOOR						
27th FLOOR						
28th FLOOR						
29th FLOOR						
30th FLOOR						
31st FLOOR						
MUMTY/MCH	106.582		106.582	106.582		
TOTAL	12227.887		12227.89	1242.148	10985.739	
TOTAL X NOS	24455.774	0	24455.77	2484.296	21971.478	0

Tower No - 9 Area Detail

FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
GROUND FL	1053.174		1053.174	34.856	1018.318	
1ST FLOOR	878.307		878.307	52.548	825.759	
2nd FLOOR	906.405		906.405	43.135	863.270	
3RD FLOOR	906.405		906.405	43.135	863.270	
4th FLOOR	906.405		906.405	43.135	863.270	
5th FLOOR	906.405		906.405	43.135	863.270	
6th FLOOR	906.405		906.405	43.135	863.270	
7th FLOOR	906.405		906.405	43.135	863.270	
8th FLOOR	906.405		906.405	43.135	863.270	
9th FLOOR	906.405		906.405	43.135	863.270	
10th FLOOR	906.405		906.405	43.135	863.270	
11th FLOOR	906.405		906.405	43.135	863.270	
12th FLOOR	906.405		906.405	43.135	863.270	
13th FLOOR	906.405		906.405	43.135	863.270	
14th FLOOR	906.405		906.405	43.135	863.270	
15th FLOOR	906.405		906.405	43.135	863.270	
16th FLOOR	906.405		906.405	43.135	863.270	
17th FLOOR	906.405		906.405	43.135	863.270	
18th FLOOR	906.405		906.405	43.135	863.270	
19th FLOOR	906.405		906.405	43.135	863.270	
20th FLOOR	906.405		906.405	43.135	863.270	
21st FLOOR	906.405		906.405	43.135	863.270	
22nd FLOOR	906.405		906.405	43.135	863.270	
23rd FLOOR	906.405		906.405	43.135	863.270	
24th FLOOR	906.405		906.405	43.135	863.270	
25th FLOOR	906.405		906.405	43.135	863.270	
26th FLOOR	906.405		906.405	43.135	863.270	
27th FLOOR	906.405		906.405	43.135	863.270	
28th FLOOR	906.405		906.405	43.135	863.270	
29th FLOOR	906.405		906.405	43.135	863.270	
30th FLOOR	906.405		906.405	43.135	863.270	
31st FLOOR	312.21		17.705	284.505	66.376	228.129
MUMTY/MCH	93.816		93.816	93.816		
TOTAL	29217.447		29217.447	1475.27	27742.177	
TOTAL X NOS	29217.447		29217.447	1475.27	27742.177	0

Tower No - 10 Area Detail

FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
GROUND FL	655.689	17.705	637.984	39.095	598.889	
1ST FLOOR	655.689	86.31	569.379	69.823	499.556	
2nd FLOOR	799.493	17.705	781.788	69.823	711.965	
3RD FLOOR	513.036	17.705	495.331			495.331
4th FLOOR	489.702	17.705	471.997	70.776	401.221	
5th FLOOR	489.702	17.705	471.997	70.776	401.221	
6th FLOOR	489.702	17.705	471.997	70.776	401.221	
7th FLOOR	489.702	17.705	471.997	70.776	401.221	
8th FLOOR	489.702	17.705	471.997	70.776	401.221	
9th FLOOR	489.702	17.705	471.997	70.776	401.221	
10th FLOOR	489.702	17.705	471.997	70.776	401.221	
11th FLOOR	489.702	17.705	471.997	70.776	401.221	
12th FLOOR	489.702	17.705	471.997	70.776	401.221	
13th FLOOR	489.702	17.705	471.997	70.776	401.221	
14th FLOOR	489.702	17.705	471.997	70.776	401.221	
15th FLOOR	489.702	17.705	471.997	70.776	401.221	
16th FLOOR	489.702	17.705	471.997	70.776	401.221	
17th FLOOR	489.702	17.705	471.997	70.776	401.221	
18th FLOOR	489.702	17.705	471.997	70.776	401.221	
19th FLOOR	489.702	17.705	471.997	70.776	401.221	
20th FLOOR	489.702	17.705	471.997	70.776	401.221	
21st FLOOR	489.702	17.705	471.997	70.776	401.221	
22nd FLOOR	489.702	17.705	471.997	70.776	401.221	
23rd FLOOR	489.702	17.705	471.997	70.776	401.221	
24th FLOOR	489.702	17.705	471.997	70.776	401.221	
25th FLOOR	489.702	17.705	471.997	70.776	401.221	
26th FLOOR	489.702	17.705	471.997	70.776	401.221	
27th FLOOR	489.702	17.705	471.997	70.776	401.221	
28th FLOOR	489.702	17.705	471.997	70.776	401.221	
29th FLOOR	489.702	17.705	471.997	70.776	401.221	
30th FLOOR	489.702	17.705	471.997	70.776	401.221	
31st FLOOR	312.21	17.705	294.505	66.376	228.129	
MUMTY/MCH	101.671		101.671	101.671		
TOTAL	16749.444	652.87	16096.574	2328.516	13272.737	495.331
TOTAL X NOS	16749.444	652.87	16096.574	2328.516	13272.737	495.331

Community facility(Clubhouse)

FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
FAR IN BSMT.-1	473.281	0	473.281	10.534	462.747	
GROUND FL	731.545	119.92	611.625	9.581	602.044	
1ST FLOOR	731.245	287.159	444.086	18.446	425.64	
TOTAL	1936.071	407.079	1528.992	38.561	1490.431	0
TOTAL X NOS	1936.071	407.079	1528.992	38.561	1490.431	0

1A

2017/III-268/9524

PROJECT	TITLE	JOB.NO.	DATE	DRN. BY	ARCHITECT'S SIGN.	OWNER'S SIGN	CONSULTANT
PROPOSED GROUP HOUSING BUILDING ON PLOT NO.GH-01/C, SECTOR - 168 NOIDA FOR.- SUNWORLD RESIDENCY PVT LTD.	REV. SUBMISSION DRAWING		03 - 06 - 15	SANDEEP	RAJIV GOEL CA/76/2361	For SUNWORLD RESIDENCY PVT. LTD. Authorised Signatory	R.N.Gupta & Associates Consulting Engineers, Architects & Valuers E - 1, Sector-55, Noida Phones - (+120) 4321556 email-info@rngcorp.com
	AREA CHART, AREA SUMMARY & DWELLINGS DETAILS	DR.NO. 1A	NORTH	CHKD. BY G.S.B.			